

CULVERT ID L

Hwy FM 140

CSJ 0748-04-042

Sta 335+03.93

Type Cross Culvert

Desc 2 ~ 28 IN X 20 IN
CMP

Arch Design 3
Des

PHOTOS LEFT



PHOTOS RIGHT



PHOTOS CENTER



ELEMENT HISTORY

AS BUILT	CSJ	0748-04-00	MODIFIED	CSJ	0748-04-03
	Date	1950		Date	1995
	Design Freq (yr)	5		Left (ft)	Right (ft)
	Design Q (cfs)	10		Ext	2.74 3.3

H&H

Design Freq (yr)	10	Q ₅ (cfs)	46	Design flow, Q _D
Existing Capacity, Q _E (cfs)	34.29	Q ₁₀ (cfs)	56	
Ponding at Q _D (ft)	.14			

VISUAL

Bridge Class	No	Left End Trt	SETP-CD-A
Overall Condition	Good	Right End Trt	SETP-CD-A
Spalling	No	Pipe Runners	No
Rusted	No	In Out Condition	Sedimentation
Buckled	No	Recommend	Remain &
Remarks	Replace end treatment.		


CULVERT ID: L

ROADSIDE

Clear Zone Available (ft)	6
Guard Fence Req'd	No
>12" Cover	Yes

LOCATION MAP

Lat 28.940739
Long -99.181827




INTERIOR PHOTO LT



INTERIOR PHOTO RT



AERIAL MAP



<https://www.google.com/maps/search/?api=1&query=28.94073966,-99.18182761>