

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

*****GENERAL NOTES*****

TxDOT Standard Specifications for Construction and Maintenance of Highways, Streets, and
Bridges (November 1, 2014)

===== **Basis of Estimate** =====

Item	Description	Rate/Area	Quant-Unit
168-6001	Vegetative Watering	1.3 GAL/SY/WEEK (11073 SY/12 WEEKS)	172.74-MG
310-6001	PRIME COAT (MULTI OPTION)	0.3 GAL/SY (32,485 SY)	6,745.5-GAL
341-6281	TACK COAT	0.1 GAL/SY (32,485 SY)	6,497.0-GAL
340-6120	LIME (HYDRATED LIME (DRY))	30 LB/SY-IN (36,587 SY)	548.8-TON
341-6028	D-GR HMA TY-C PG70-22	110 LB/SY-IN (32,485 SY)	5,360-TON
341-6049	D-GR HMA TY-D PG76-22	110 LB/SY-IN (32,485 SY)	5,360-TON
6210-XXXX	PVC MOISTURE BARRIER	0.41 SY/LF (4682 LF)	1,934-TON

--General--

- G-3 Contact the Engineer or the City when construction operations are within 400 feet of a signalized intersection to determine/verify the location of loop detectors, conduit, ground-boxes, etc. Repair or replace any signal equipment damaged by construction operations. The method of repair or replacement shall be pre-approved and inspected. Depending on the type and extent of the damage, the Engineer reserves the right to perform the repair or replacement work and the Contractor will be billed for this work.
- G-5 To better fit field conditions, the cross sections may be varied when approved.
- G-6 If there are waste areas or material source areas, follow the Texas Aggregate Quarry and Pit Safety Act requirements.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

- G-7 Any materials removed and not reused and determined to be salvageable shall be stored within the project limits at an approved location or delivered undamaged to the storage yard as directed. Properly dispose unsalvageable materials in accordance with local, state, and federal regulations. Deface traffic signs so that they will not reappear in public as signs.
- G-8 Any sign panels that are adjusted or removed and replaced, shall be done the same workday unless otherwise approved. This work shall be considered subsidiary to Item 502.
- G-9 Notify the Engineer at least two weeks prior to a proposed traffic pattern change(s) that will require a revision to traffic signals.
- G-10 Locate and reference all manholes and valves within the construction area with station and offset. Each manhole and valve shall be identified by its owner. No roadwork will begin until this list has been submitted. Gas valves have to be accessible at all times, therefore; temp. CTB, material stock piles, etc. cannot be placed over these valves.
- G-11 Construct all manholes and valves to final pavement elevations prior to the final mat of ACP. If, between the final elevation adjustment and the final mat of ACP, the manholes and valves are going to be exposed to traffic, place temporary asphalt around the manhole and valve to provide a +/- 50:1 taper. The cost of elevation adjustment will be part of the manhole and valve work, and asphalt tapers are considered subsidiary to Item 502.

Work times are from 8:00 am to 5:00 pm.

Irrigation heads and fixture relocations in conflict with the proposed improvements are not paid for separately but are subsidiary to various bid items.

Buildings and Structures must be protected from concrete splash at all times. The Contractor is to install a material approved by the Engineer which will guard the buildings against concrete splash. This work is considered subsidiary to Item 531 and will not be paid separately. If concrete splash litters a building facade the Contractor, at their expense, is responsible for cleaning and remedying the concrete as approved by the Engineer.

Grade street intersections and median openings for surface drainage.

Sweep and remove all litter, construction debris and surplus material on the right-of-way within the project limits to keep the jobsite neat at all times. Keep roadways and sidewalks free of sediment. Consider subsidiary to pertinent items.

Construct all ramps, sidewalks, steps, curb ramps, handrails, pedestrian push buttons, and other pedestrian elements in accordance with Proposed Guidelines for Pedestrian Facilities in the Public Right-of-Way (PROWAG) issued by the United States Access Board. Maintain one copy of PROWAG at the project site at all times.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

When working near aerial electrical lines and / or utility poles, provide adequate safety measures, as needed, to comply with the appropriate sections of Federal and State regulations. For electrical lines and poles shown in the plans, if the lines need to be de-energized and / or if poles require bracing, contact the electrical company to coordinate the de-energizing and bracing. Work pertaining to de-energizing lines, bracing poles and any other protective measures required will not be paid at the expense of City of New Braunfels.

Dust control is to be performed a minimum of three times per day and as needed during construction (including weekends). Dust control will be considered subsidiary to the various bid items, and will not be paid for directly.

Personnel will be experienced in items of work in contract. Safety vests and hard hats will be pre-approved and worn at all times when outside vehicles within the work area.

Pavement markers will be left in place until such time as they are in conflict with the work in progress.

Referencing of all existing striping and pavement markings prior to beginning paving operations shall be the Contractor's responsibility.

All pavement markings and/or striping that are in conflict with traffic operations will be removed by the Contractor. Such removal will be considered subsidiary to the various bid items, and will not be paid for directly.

Existing storm sewers and utilities are shown from the best available information. Verify the location of all underground facilities prior to starting work.

Provide temporary drain openings at all low points or other drainage structures, as required, at the Contractor's expense.

Remove any obstructions to existing drainage due to the Contractor's operations, as required, at the Contractor's expense.

If construction has not commenced within one-year of City approval for construction inspection, that approval is no longer valid.

The most current editions of the Texas Department of Transportation Standard Specifications for Construction of Highways, Streets and Bridges shall be followed for all construction except as amended by the City of New Braunfels Standard Details.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

All responsibility for the adequacy of these plans remains with the engineer of record. In accepting these plans, the City of New Braunfels must rely upon the adequacy of the work of the engineer of record.

Prior to the start of construction the Contractor shall contact the City of New Braunfels to set a preconstruction meeting. A 48-hour advanced notification is required for all inspection and meeting requests.

For Public Infrastructure Permit (**SC**) or Grading Permit (**GP**) Projects:

- For inspections, you must call before 12:00 p.m., 48 hours prior to your inspection request.
- Each inspection will be allotted 1 hour unless you request for more time.
- Once your request has been accepted, you will receive a call from the City of New Braunfels Inspector.

For Commercial Permit (**CP**) Projects:

- All inspections are to be called in at 830-221-4068 or,
- Faxed in at 830-608-2117 or,
- E-mailed at inspections@nbtexas.org.

It is the Contractor's responsibility to see that all temporary and permanent traffic control devices are properly installed and maintained in accordance with the plans and latest edition of the Texas Manual on Uniform Traffic Control Devices. If, in the opinion of the engineering representative and the construction inspector, the barricades and signs do not conform to established standards or are incorrectly placed or are insufficient in quantity to protect the general public, the construction inspector shall have the option to stop operations until such time as the conditions are corrected. If the need arises, additional temporary traffic control devices may be ordered by the Engineering representative at the Contractor's expense.

Type II B-B blue reflective raised pavement marker shall be installed in the center of the roadway adjacent to all fire hydrants. In locations where hydrants are situated on corners, blue reflective raised pavement markers shall be installed on both approaches which front the hydrant. The raised pavement marker shall meet TxDOT material, epoxy and adhesive specifications.

Groundwater

It shall be the responsibility of the developer, Contractor, subcontractors, builders, City, and project engineer to immediately notify the Office of the City Engineer and project engineer if the presence of groundwater within the site is evident. Upon notification the project

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

engineer shall respond with plan revisions for the mitigation of the groundwater issue. The City Engineer shall respond within two (2) business days upon receipt of the mitigation plan. All construction activity, impacted by the discovery of groundwater, shall be suspended until the City Engineer grants a written approval of the groundwater mitigation plan.

Record Drawings

As per Platting Ordinance Section 118-38m.: When all of the improvements are found to be constructed and completed in accordance with the approved plans and specifications and with the City's standards, and upon receipt of one set of "Record Drawing" plans, and a digital copy of all plans (PDF) the City Engineer shall accept such improvements for the City of New Braunfels, subject to the guaranty of material and workmanship provisions in this Section.

Construction Note

Contractor is responsible to ensure that erosion control measures and stormwater control sufficient to mitigate off site impacts are in place at all stages of construction.

Drainage Note

Drainage improvements sufficient to mitigate the impact of construction shall be installed prior to adding impervious cover.

Soils Testing

Proctors shall be sampled from on site material (on site is defined as limits of construction for this plan set) and a copy of the proctor results shall be delivered to the City of New Braunfels Street Inspector prior to any density tests.

Roadway

All roadway compaction tests shall be the responsibility of the developer's Geotechnical Engineer. Flexible base or fill/embankment material shall be placed in uniform layers not to exceed eight inches (8") loose. The required density for the fill/embankment material shall meet the requirements of TxDOT's Specification Item 132. The required density for the flexible base material shall meet the requirements of TxDOT's Specification Item 247. Each layer of material, inclusive of subgrade, shall be compacted as specified and tested for density and moisture in accordance with Test Methods TEX-113-E, TEX-114-E, TEX-115-E. The number and location of required tests shall be determined by the Geotechnical Engineer and approved by the City of New Braunfels Street Inspector. At a minimum, tests shall be taken every 200 LF for each lift. Upon completion of testing, the Geotechnical Engineer will provide the City of New Braunfels Street Inspector with all testing documentation and a certification stating that the placement of flexible

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

Drainage Trench Compaction

All utility trench compaction tests within the street pavement/sidewalk section shall be the responsibility of the developer's Geotechnical Engineer. Fill material shall be placed in uniform layers not to exceed twelve inches (12") loose. Determine the maximum lift thickness based on the ability of the compacting operation and equipment used to meet the required density. Each layer of material shall be compacted to a minimum 95% density and tested for density and moisture in accordance with Test Methods TEX-113-E, TEX-114-E, TEX-115-E. The number and location of required tests shall be determined by the Geotechnical Engineer and approved by the City of New Braunfels Street Inspector. At a minimum, tests shall be taken every 200 LF for each lift and every other service line. Upon completion of testing the Geotechnical Engineer shall provide the City of New Braunfels Street Inspector with all testing documentation and a certification stating that the placement of fill material has been completed in accordance with the plans. Additional density tests may be requested by the City of New Braunfels Inspector.

Curb Cut Due To Construction Of New Right-Of-Way Construction

Sawcut existing streets and match to new construction. Sawcut existing curb to tie into existing construction. Saw cutting existing pavement, concrete, and riprap is not paid for separately but is subsidiary to various bid items.

Construction Stabilized Entrance

Sawcut curb for construction entrance. Stabilized construction area shall be constructed as indicated on the plans and maintained so that construction debris does not fall within the city right-of-way. Right- of-way must be cleared from mud, rocks, etc. at all times.

Signing And Pavement Marking Plan Notes

The Contractor shall furnish and install all regulatory and warning signs, streets name signs and sign mounts in accordance with approved engineering plans. The City will inspect all signs at final inspection.

The Contractor shall install all pavement markings in accordance with approved engineering plans. The Contractor shall notify the City at least twenty-four (24) hours prior to the installation of all sealer and final markings. The City will inspect all markings at final application.

References to manufacturer's trade name or catalog numbers are for the purpose of identification only. Similar materials from other manufacturers are permitted if they are of equal quality, comply with the specifications for this project, and are approved, except for roadway illumination, electrical, and traffic signal items.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

The cost for materials, labor, and incidentals to provide a minimum 14'-wide driving surface for traffic across the roadway and for ingress and egress to private property in accordance with Section 7.2.4 of the standard specifications is subsidiary to the various bid items. Restore access roadways to their original condition upon completing construction.

--Item 5--

5-2 Taper ACP placed at curb inlets, traffic inlets and slotted drains.

5-4A. Prior to letting, bidders may obtain a free computer diskette or a computerized transfer of files (from the Engineer's office) that contains the earthwork information.

5-7 Provide a non-intrusive back-up alarm system on all heavy equipment used in close proximity to residential areas. This item is subsidiary to various bid items.

--Item 6--

6-1 Show the stockpile lot and/or sub lot numbers on all tickets for all materials.

--Item 7--

7-1 The project's total disturbed area is 11.30 acres. The disturbed area in all project locations and Contractor project specific locations (PSL's), within 1/4 mile of the project limits, will further establish the authorization requirements for storm water discharges. The Contractor will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. Obtain any required authorization from the TCEQ for any PSL's on or off the ROW. When the total area disturbed on the project and PSL's within 1/4 mile of the project exceeds 5 acres, provide a copy of the Contractor NOI for PSL's to the Engineer (to the appropriate MS4 operator when the project is on an off-state system route).

7-3 Notify the Engineer of the disturbed acreage within one (1) mile of the project limits. Obtain authorization from the TCEQ for Contractor PSL's for construction support activities on or off ROW.

7-5 No significant traffic generators events identified.

--Item 8--

8-1 Working days will be computed and charged in accordance with Article 8.3.1.5: Calendar Day.

8-1A Create and maintain a bar chart schedule.

--Item 9--

Show proof of certification by the Texas Commission on Law Enforcement Standards.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

All law enforcement personnel used in Work Zone Traffic Control shall be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement Personnel in Work Zones" (Course #133119) which can be found online at the following site: www.nhi.fhwa.dot.gov

Certificates of completion should be available to all who finish the course. These should be kept by the officers in order to substantiate completion when reporting to the work site.

--Item 100--

100-1 Begin clearing operations after trees and other areas of vegetation to be protected have been identified and approved. Install fencing around features to be protected as shown in the plans or directed. Coordinate all right of way clearing operations with the SW3P.

100-2 Trim and remove brush and trees as needed for construction operations. Obtain approval for proposed method of tree and brush trimming and removal. Vertical flailing equipment is not allowed. Treat damaged or cut branches, roots and/or stumps of all oak trees with a commercial tree wound dressing. Disinfect all pruning tools with a solution of 70% alcohol before moving from one tree to another. Unless otherwise approved remove all resulting vegetative debris from the ROW within 24 hours. The Engineer can stop all construction operations if the dressing, cut and removal requirements are not followed.

--Item 110--

110-1 Where excavation extends beyond a right of way fence, remove and replace the fence to a comparable condition. This work shall be considered subsidiary to the bid item.

--Item 132--

132-1 At no time shall the retaining wall backfill material exceed the adjacent embankment operation by more than one embankment lift. At no time will the embankment adjacent to the retaining wall backfill exceed the wall backfill by any elevation.

--Item 160--

160-1 Approximately 1220 CY of existing topsoil is required. Existing topsoil within the ROW may be windrowed or stockpiled (as approved) for later use under this Item. Place erosion control measures for the stockpile and/or windrow.

--Item 162--

162-1 Furnish and place block grass sod of the same species as the surrounding vegetation.

--Item 164--

Seeding for the purpose of establishing vegetation within constructed earthen channels, basins and disturbed areas shall be conducted in accordance with Item 164 (Seeding for Erosion Control) of TxDOT's Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges manual. Only seed types and mixes specified for the San Antonio District

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

(District 15) in Tables 1 and 2 under Item 164 shall be utilized. During the Cool Season (Sept 1-Nov 30), Cereal Rye and seed species specified for the San Antonio District in Table 3 may be used. For Cool Season seeding applications, cool season seed mixes shall be used in conjunction with seed mixes for the San Antonio District as specified in Table 1 and 2 under Item 164.

It may be deemed necessary to incorporate topsoil and soil amendments (i.e. compost/ fertilizer) into existing soil in order to facilitate vegetation growth. Topsoil, compost and fertilizer additions shall be conducted according to Items 160, 161 and 166 of TxDOT's Standard Specifications manual, respectively.

Watering may also be necessary to facilitate and expedite the sprouting and growth of vegetation. Item 168 of TxDOT's Standard Specifications manual shall be adhered to for vegetative watering.

If extended drought conditions exist that hinder or prohibit the growth and establishment of vegetation, the contract/ developer shall provide a plan to the City of New Braunfels describing the measures that will be taken to stabilize earthen drainage infrastructure until a time when growing conditions become more favorable.

--Item 168--

168-1

Apply vegetative watering as needed to supplement natural rainfall during the vegetation establishment period. Plan quantity of irrigation water is based on the application of a total of 1.3 gal of water each week for each sq. yd. of area that is sodded or seeded. Establishment time is estimated to be 12 weeks or minimum 75% establishment for both sod and permanent seed mixes. Temporary seeding will require less time for establishment. Provide a schedule and coordinate watering cycles and rates per cycle with the Engineer. Obtain approval if the quantity of water to be applied is expected to exceed the plan quantity. Adjust the amount of water applied with each cycle and the number of cycles each wk. according to actual site conditions. Drought or other conditions, as determined by the Engineer, may require the application of supplemental irrigation during hours other than normal working hours.

--Item 247--

Provide Flexible Base material as approved by the City.

--Item 260--

Provide Hydrated Lime Slurry as approved by the Engineer.

--Item 310--

Provide Prime Coat as approved by the Engineer.

--Item 275--

275-1 The Engineer will designate a target cement content and optimum moisture content necessary to produce a stabilized mixture that meets the strength requirements and moisture

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

susceptibility requirements shown in Table 1. The Contractor shall furnish the Engineer with representative samples of the materials to be used in production of the cement treated base.

Table 1
Requirements for Cement Treatment

Content (by dry weight of base)		
Unconfined Compressive Strength	Part I	
Strength after Moisture Soak (min.)	Part I (10 day capillary soak)	7-Day Unconfined Compressive

Microcracking will be required in accordance with Item 275.4.7.

--Item 320—

- 320-1 Construct all longitudinal ACP joints adjacent to a travel lane with a joint maker device that will create a 3:1 to 6:1 taper. For placement of 2 inches or more, the device shall provide a maximum 1/2 inch vertical edge. Taper outside edges (next to the grass) or backfill (shoulder-up) the same day.
- 320-2 Provide a material transfer device capable of providing a continuous flow of material to the paver. The material transfer device will consist of a windrow elevator or better.

--Item 340, 341, 342, 344, 346, 347, & 348—

Asphaltic concrete pavement shall be the type of hot mix asphalt as defined in TxDOT's standard specifications for current TxDOT Standard Specifications for Construction of Highways, Street and Bridges.

The City of New Braunfels will not accept the use of Recycled Asphalt Pavement (RAP) or Recycled Asphalt Shingles (RAS) in asphalt mixtures for new roadways. Any debris inclusions within new asphalt pavements will result in asphalt removal and replacement from curb to curb for limits to be determined by the City of New Braunfels.

The asphaltic concrete pavement surface course shall be plant mixed, hot laid type "D" meeting the specification requirements of TxDOT Item 340. The asphaltic concrete pavement sub-surface courses shall be plant mixed, hot laid type "B" meeting the specification requirements of TxDOT Item 340. The mixture shall be designed per the design requirements specified in TxDOT Item 340 and shall be compacted to between 91 and 95 percent of the maximum theoretical density as determined by TxDOT test method TEX-227-F. Place the mixture when the roadway surface temperature is at or above 60°F. Complete all compaction operations before the pavement

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

temperature drops below 160°F. The asphalt cement content by percent of total mixture weight shall fall within a tolerance of +0.5 percent from a specific mix design.

1. Table 10, in Item 340, Table 10 in Item 341 and Table 11 in Item 344, Hamburg Wheel Test Requirements tested in accordance with Tex-242-F are changed for PG 64-22 or lower and PG 70-22. Minimum number of passes at 1/2" Rut Depth, Tested at 122 degrees F will be 5,000 and 10,000 respectively.
2. Design all mixture types using a target laboratory-molded density of 96.5%, when the Texas Gyrator Compactor is utilized. Increase the target laboratory-molded density to 97.0% or 97.5% at the Contractor's discretion. When utilizing SGC, design all mixture types at 50 gyrations (N-Design) and a target laboratory-molded density of 96.0%, but may be reduced to no less than 35 gyrations at the Contractor's discretion.
3. The asphalt plant shall have truck scales as defined in Item 520. Give three weight tickets bearing the date, the truck number, the gross, net & tare weights to the truck driver for the State inspector at the spreading and finishing operation. Trucks may be required to weigh on public scales or portable platform scales to verify the weight of the ticket.
4. Submit a copy of the Tex 233-F production charts on a weekly basis. At the end of the ACP work, provide all originals.
5. Crushing of aggregate for hot mix and immediate use for production of the mix is not allowed. Stockpile the aggregate until enough material is available for five days of production unless prior approval is provided. Hold a pre-placement meeting one month prior to the placement of the hot mix.
6. The main purpose of hot mix cores taken by the City are for payment calculations. If (for quality control purposes) the core information is needed sooner, take additional cores.
7. Do not use diesel or solvents as asphalt release agents in production, transportation, or construction.

Schedule lay-down placement where uneven travel lanes are minimized and eliminated weekly.
8. The use of Recycled Asphalt Pavement (RAP) and Recycled Asphalt Shingles (RAS) will not be allowed on the final riding surface.

Materials testing is to be completed by the City.

Minimum Roadway Placement Temperature
--Item 340, 341, & 344--

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

1. Place mixture when the roadway surface temperature is equal to or higher than listed in Table 1 unless otherwise approved or shown on the plans. Measure the roadway surface temperature with a hand-held thermal camera or infrared thermometer. Placement may be allowed to begin prior to the roadway surface reaching the required temperature if conditions are such that the roadway surface will reach the required temperature within 2 hrs. of beginning placement operations. Place mixtures only when weather and moisture conditions of the roadway surface are suitable in the opinion of the Engineer. The Engineer may restrict the Contractor from paving if the ambient temperature is likely to drop below 32°F within 12 hr. of paving.

Table 1
Minimum Pavement Surface Temperatures

		Minimum Pavement Surface Temperatures in Degrees Fahrenheit *	
Specification Item Number	High Temperature Binder Grade	Subsurface Layers or Night Paving Operations	Surface Layers Placed in Daylight Operations
340, 341, & 344	PG 64	45	50
	PG 70	55	60
	PG 76	60	60

* Except for PG 64, may pave at temperatures 10° F lower than the values shown in Table 1 when utilizing a Material Transfer Vehicle that is capable of providing a remixing, and continuous flow of material from the haul truck to the paver, such as a Roadtec SM-2500e/ex, that eliminates thermal segregation. In these cases, use either an infrared bar attached to the paver, or a hand held thermal camera or infrared thermometer, or a hand held infrared thermometer operated in accordance with Text Method 244-F to demonstrate that the uncompacted mat has no more than 10° F of thermal segregation.

Substitute Binder

--Item 340, 341 & 344--

The Contractor may use a substitute PG binder listed below in Table 1 instead of the PG binder originally specified in Table 5 of the Standard Specification, if the substitute PG binder and mixture made with the substitute PG binder meet the following:

- ◆ The substitute binder meets the specification requirements for the substitute binder grade in accordance with Section 300.2.10., "Performance-Graded Binders;" and

The mixture has less than 10.0 mm of rutting on the Hamburg Wheel test (Tex-242-F) after the number of passes required for the originally specified binder. Use of substitute PG binders may

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

only be allowed at the discretion of the Engineer if the Hamburg Wheel test results are between 10.0 mm and 12.5 mm

Table 1
Allowable Substitute PG Binders and Maximum Recycled Binder Ratios

Originally Specified PG Binder	Allowable Substitute PG Binder	Maximum Ratio of Recycled Binder ¹ to Total Binder (%)		
		Surface	Intermediate	Base
HMA				
76-22 ^{2,5}	70-22	20.0	20.0	20.0
	70-28	20.0	35.0	40.0
70-22 ²	64-22	20.0	20.0	20.0
	64-28 or 58-28	20.0	35.0	40.0
64-22 ²	58-28	20.0	35.0	40.0
76-28 ^{2,5}	70-28	20.0	20.0	20.0
70-28 ²	64-28 or 58-28	20.0	20.0	20.0
	64-34 or 58-34	20.0	35.0	40.0
64-28 ²	58-28	20.0	20.0	20.0
	58-34	20.0	35.0	40.0
WMA ³				
76-22 ^{2,5}	70- 22	20.0	35.0	40.0
70-22 ²	64-22 or 58-28	20.0	35.0	40.0
64-22 ⁴	58-28	20.0	35.0	40.0
76-28 ^{2,5}	70-28	20.0	35.0	40.0
70-28 ²	64-28 or 58-28	20.0	35.0	40.0
64-28 ⁴	58-28	20.0	35.0	40.0

1. Combined recycled binder from RAP and RAS.
2. Use no more than 20.0% recycled binder when using this originally specified PG binder.
3. WMA as defined in Section 341.2.6.2., "Warm Mix Asphalt (WMA)."
4. When used with WMA, this originally specified PG binder is allowed for use at the maximum recycled binder ratios shown in this table.
5. No more than 1-PG grade lower than what is show on the plans will be permitted for Surface mixtures

--Item 479--

All wastewater utility adjustments under this Project are subject to the inspection and acceptance by New Braunfels Utilities (NBU) or a duly authorized agent of NBU. Contractor is responsible for providing written notice to NBU Water & Wastewater no less than 48 hours in advance of commencing work under this Project. All work shall conform to the current New Braunfels Utilities Water Systems Connection/Construction Policy.

--Item 403--

The Contractor and/or Contractor's Engineer who selects and designs the temporary shoring is responsible for the overall (global) stability calculations as well as internal stability and sliding calculations (including mat and soil nail pullout) as per the TxDOT Bridge Division Geotechnical Manual. If the Contractor chooses a Temporary Earth Retaining Wall for Temporary Shoring, then the Contractor and/or Contractor's Engineer is required also to provide wire struts as shown on these plans. Designs for any type of Retaining Wall used for Temporary Special Shoring shall conform to the TXDOT Geotechnical Manual Chapter 6: Retaining Walls.

403-1

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

--Item 421--

- 421-1 Use an automated ticket that contains the same information as TxDOT's ticket. Submit the ticket for approval prior to use. The concrete producer will contact the District Laboratory or the Engineer's Office (outside the San Antonio area) to inform TxDOT of scheduled structural concrete batching. Structural concrete includes bridge drill shafts, columns, caps, abutments, deck or top slabs of direct traffic culverts.

Entrained air is allowed for Class P and Class HES concrete only. Air content testing is waived for all classes of concrete.

--Item 422--

- 422-1 For construction of approach slabs, longitudinal joints shall be placed on lane lines. Joints may be either a saw-cut crack control joint or a construction joint. Saw cut joints shall terminate 1'-0" before reaching the edge of the slab, must be saw cut as soon as possible after placement of concrete, and will be cut within 12 hours of concrete placement. Once sawing begins, it should be a continuous operation and should only be stopped if raveling occurs. Saw cut will be to a depth of 1.5" and filled with approved joint sealant.

--Item 423--

- 423-1 The backfill material for pre cast retaining walls shall be approved before placement. Build stockpile(s) in lifts not to exceed 2 feet and a minimum working face of not less than 10 feet, but not more than 20 feet.

- 423-3 Use the approved Mechanically Stabilized Earth (MSE) wall systems listed at:
http://www.dot.state.tx.us/business/contractors_consultants/bridge/retaining_wall.htm

When proprietary wall systems are used, a qualified representative of the retaining wall manufacturer must be available upon request during wall construction. As requested or required the manufacturer's representative must be on site to assist with the initial stages of wall construction, provide training to the Contractor wall crew and ensure proper interpretation of MSE wall shop drawings and details. Specific attention must be given to nonstandard wall installation details. The Contractor's wall crew foreman must be on site for the duration of wall construction. Any change to the wall crew foreman may require additional training by the wall supplier. The Contractor will ensure that the retaining walls are installed per the details presented in the construction drawings and as per the proprietary wall system requirements. The Engineer reserves the right to suspend wall construction activities due to any construction issue encountered.

Horizontal and vertical nail spacing on temp or permanent soil nail walls shall not exceed 4 ft.

Type DS material will be required on MSE walls in the area of the reinforcement mats.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

--Item 432--

432-1 In all riprap slopes, provide 3 inch diameter weep holes at 10 foot maximum spacing and backed with loose graded gravel or crushed stone and galvanized hardware cloth.

432-2 In areas where guard fence posts are to be placed in riprap, the riprap shall have an 18 inch +/-blocked out area (round or square). Blocked out areas shall be backfilled with 2 sack flowable backfill and considered subsidiary to the various bid items.

--Item 465--

465-1 Concrete Class B invert shaping is required at all inlets, manholes and junction boxes in order to insure positive flow. The material and work performed for the placement of the inverts shall be considered subsidiary to this item.

Provide for the safety and health of employees and abide by all OSHA Standards and Regulations. All costs incurred for proper management, shall be subsidiary to this Item.

--Item 496--

496-1 The Contractor will submit a demolition plan for all structures to be replaced and/or removed in accordance with Item 496.

--Item 500--

500-1 "Materials on Hand" payments will not be considered in determining percentages for mobilization payments.

--Item 502—

Prior to beginning construction, the City shall approve the routing of traffic and sequence of work.

Additional signs and barricades as directed by the Engineer shall be considered subsidiary to Item 502.

Construct the project in phases per the Traffic Control Plan in phase order. The Contractor shall not begin construction on a subsequent phase until the active phase is considered complete. A phase is considered complete when all pavement section layers except final riding surface have been constructed; substantially useable sidewalk and driveways have been constructed; and vegetation re-establishment has begun.

The Contractor shall limit impacts to individual driveways to a 3-day turnaround time from demolition to poured concrete. The Contractor shall maintain access to each driveway during construction except during this 3-day period. Construct temporary ramps to maintain access to driveways and city streets as directed by the Engineer. Temporary ramp construction is subsidiary to Item 502.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

- 502-1 Place standard markings no later than 14 days after surface treatment operations are completed.
- 502-2 When advanced warning flashing arrow panels and/or changeable message sign is specified, have one standby unit in good condition at the job site. Standby time shall be considered subsidiary to the bid item.
- 502-3 Treat the pavement drop-offs as shown in the TCP.
- 502-4 After written notification, the time frame to provide properly maintained signs and barricades before considered in non-compliance is 48 hours from receipt of the notification. Failure to make corrections as noted may result in payment for this item being withheld.
- 502-5 There are traffic signals at the intersection of Klein Rd and FM 725. Keep the signals in operation except when necessary for specific installation operations.
- 502-6 Moving an existing sign to a temporary location is subsidiary to this Item. Installations with permanent supports at permanent locations will be paid for under the applicable bid item (s).
- 502-7 Mount temporary mailboxes on plastic drum in accordance with Compliant Work Zone Traffic Control Devices, Section K. Temporary mailboxes shall be located for postal delivery by vehicle at all times. Mounting and moving the mailbox as needed for the various construction phases is subsidiary to this Item.
- 502-8 Notify the Engineer in writing 10 business days in advance of any temporary or permanent lane, closures/detours, restrictions to lane widths, alterations to vertical clearances, or modifications to radii. Any other modifications to the roadway that may adversely affect the mobility of oversized/overweight trucks also require 10 business days advance written notice to the Engineer. Unless shown in the TCP, no lane closures are allowed during special events. Lane closures will not be allowed if this reporting requirement is not met.
- 502-9 Avoid placing stockpiles within the roadway's horizontal clear zone. If a stockpile is placed within the clear zone, address in accordance with the TMUTCD.
- 502-10 Do not place barricades, signs, or any other traffic control devices where they interfere with sight distance at driveways or side streets.
- 502-11 In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee available to respond on the project for emergencies and for taking corrective measures within 2 hours or within a reasonable time frame as specified by the Engineer.
- 502-13 If Nighttime work is required and work is not behind positive barrier then full TY 3 reflective gear is required to be worn by all workers, hard hat halos are required to be worn by the flaggers

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

at flagging stations, TY III barricades are required to be spaced at 500 ft, and a mandatory night work meeting is required.

Prior to beginning construction, the Engineer shall approve the routing of traffic and sequence of work.

Additional signs and barricades as directed by the Engineer shall be considered subsidiary to Item 502.

Wash the channelizing devices and barricades following each rainfall or snowfall event and at times deemed necessary by the Engineer.

Fill any holes left by barricade or sign supports and restore the area to its original condition. "Sidewalk Closed" (R9-9) signs are to be used while work is ongoing. See TxDOT standard WZ(BTS-2)-13 for more details.

--Item 506--

506-1 An Inspector will perform a regularly scheduled SWP3 inspection every 7 calendar days.

506-3 Failure to address items noted on the SW3P inspection report within two report cycles may result in the Department stopping all construction operations, exclusive of time charges, or withholding that month's estimate until the SW3P deficiencies are corrected unless the Engineer determines that the area is too wet to correct SW3P deficiencies.

Erosion control logs, sandbags and other BMPs will be placed and relocated as directed by the Engineer in order to comply fully with the SW3P requirements.

Water pumped off the project must have sediment and any other solids in suspension removed before discharging.

--Item 512--

New Single Slope or F-Shape CTB (cast in accordance with the Standard Sheets in the plans) may be furnished or the same pre-used shapes (that meet the requirements of this Item) may be furnished. New Safety Shape (New-Jersey) CTB is not allowed, but pre-used New-Jersey (that meets the requirements of this Item) may be furnished. More than one type may be furnished but do not mix the types when placed along the roadway.

--Item 529--

529-1 Class "C" concrete is required for machine extruded curb.

--Item 530--

Use Class A Concrete for all concrete driveways.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

Contractor is responsible for notifying residents at least 72 hours in advance prior to excavating driveways. Contractor should not take longer than 3 days to complete the construction of the driveways once excavation begins, weather pending.

--Item 531--

531-1

The curb ramp locations shown in the plans have taken into account the geometric features of the intersection, utilities, signage, and pavement markings. If anything changes during construction, the location of curb ramps must be adjusted to ensure they meet PROWAG requirements.

Truncated dome pavers are prohibited.

All detectable warning surfaces are to be prefabricated panels constructed of cast iron or composite materials of contrasting color to the surrounding material, as approved by the Engineer.

Proposed curb ramps, sidewalks, curbs, and riprap are to be doweled 6-in minimum, unless otherwise shown, into existing concrete using 1/2-in reinforcement placed on 12-in centers.

Curb wall along ramps and landings, unless otherwise shown on the plans, is not paid for separately but is subsidiary to the ramp or landing. If the wall extends above the plane of the landing, retaining wall (unless otherwise noted on the plans) should be utilized. Retaining wall quantities are shown for Contractor information only, payment is subsidiary to Item 531 Sidewalks. See special details sheets for more information.

Areas labeled with a "T" on the construction drawings allow the Contractor to transition to existing conditions. Slope and grade of all transitions must be approved by the Engineer.

Each planar element along the accessible route indicates the maximum slope and cross slope for that element as defined in the plans – in many cases the element can be constructed to achieve the design intent at or below the maximum slope for that element. With the approval of the Engineer, the Contractor may extend the length of ramps or sloped sidewalks to the next planar element (level sidewalk, landing, transition, or driveway) or until the point at which the ramp or sloped sidewalk reaches the height of the adjacent curb, whichever is shorter, in order to achieve the design intent.

Construct compliant curb ramps based upon referenced design criteria, PROWAG and TxDOT Pedestrian Facilities Standards. All intersection corners are unique and it may be necessary to use various combinations of ramp elements to achieve a compliant ramp configuration.

Review the curb ramp location and layout with the inspector prior to demolition so that both parties agree that the curb ramp can be installed properly. Should it become apparent at any time during the ramp layout and construction process that a curb ramp cannot be installed as indicated on the plans, promptly notify the inspector.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

Any approval, inspection, or checking of the Contractor's layout and the acceptance of all or any part of it shall not relieve the Contractor of his responsibility to secure the proper dimensions, grades and elevations of the various parts of the work.

Contractor is to match existing concrete color and texturing at various locations which, as directed by the Engineer, require matching.

The furnishing and installation of the sand cushion in the proposed sidewalks, sidewalk ramps and driveways will not be paid for directly but shall be considered subsidiary to this bid item.

The furnishing and installation of pipe underdrains, filter material, and other incidentals to ensure proper drainage of special concrete sidewalk with retaining wall per Concrete Sidewalk (Special)(Type B) will not be paid for directly but shall be considered subsidiary to this bid item and in accordance with Item 531.

Removal of existing concrete, surfaces, asphalt, base material, sign posts, miscellaneous materials, and all incidentals is included in this pay item within the footprint of the proposed work. If additional work related to the removal of existing is required beyond the quantity identified for Contractors information only, no additional payment will be made.

In areas where there is no curb fillet or concrete pavement, saw cut the existing curb and gutter and remove the curb.

When lack of right of way width or obstructions creates insufficient space, the ramp may be relocated within the right of way when authorized by the Engineer. All deficient ramps will be removed and replaced at the Contractor's expense.

For curb ramps, form tooled joints on each side of the ramp section where it meets a flare or curb wall, at each break in ramp slope or geometry, and at intervals equivalent to the width of the sidewalk for the purpose of cracking control. Place expansion joint material between proposed ramps and existing concrete; between proposed sidewalk and utility poles, guy wires, vent pipes, stand pipes and as directed.

Construct concrete steps, as shown in the plans or as directed by the Engineer, measured by the cubic yard and paid for as Item 420 Concrete Substructures.

--Item 560--

Move and replace all mailboxes within the project limits such that they may be served by the mail carrier from a vehicle at all times during and after construction. This work will be considered subsidiary to the various bid items of this contract.

If a permanent (concrete or brick) mailbox is called out to be relocated, rebuild and reset the existing mailbox in the proposed location.

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

MBGF posts shall be round with domed tops, and not painted. If 10 or less timber posts are needed, they may be purchased locally and will be accepted by visual inspection.

540-2 Guard fence posts placed in proposed and/or existing areas of riprap, sidewalks or other concrete shall have an 18 inch +/- (square or round) block out in the concrete. After the posts are installed, the blocked out area shall be topped off with 4 inches of low strength grout/mortar consisting of about 1 sack of cement per cubic yard of mix.

540-4 When connecting a Thrie-Beam to a concrete wingwall, bridge rail, CTB, etc., drill the holes for bolt placement using rotary or core type equipment. Use a core type drill when reinforcing steel is encountered. Do not use percussion or impact drilling. Repair damage to the concrete and spalls exceeding 1/2" from the edge of the hole.

--Item 666--

666-1 Use TY II material (vs. an acrylic or epoxy) as the sealer for the TY I markings, place the TY II a minimum of 14 calendar days (to provide adequate curing) before placing the TY I markings.

Median nose pavement marking materials are to be approved by the Engineer.

--Item 672--

672-1 Place all adhesive material directly from the heated dispenser to the pavement. Do not use portable or non-heated containers. Use adhesive of sufficient thickness so that when the marker is pressed into the adhesive, 1/8" or more adhesive will remain under 100% of the marker. The adhesive should extend not less than 1/2" but not more than 1 1/2" beyond the perimeter of the marker.

--Item 677--

677-1 Obtain approval before using the mechanical method for the elimination of existing thermoplastic pavement markings.

--Item 680--

680-1 Furnish and install all required materials and equipment necessary for the complete and operating traffic signal installation at the following intersections:

1. FM 725 at Klein Rd

680-2 The locations shown on the plans for signal pole foundations, controller foundations, conduit and other items may be adjusted to better fit field conditions as approved.

680-3 High pressure sodium lamps shall meet ANSI C78 requirements and shall be the type that extinguishes at the end of usable lamp life and remains extinguished without cycling. 400 watt lamps shall contain less than 4.0 MG of mercury. 250 watt lamps shall contain less than 3.0 MG

Project: NB 18-026

County: Guadalupe

Highway: Klein Rd Ph 2

of mercury. Lamps shall be lead free. Lamps shall pass the Federal Toxic Characteristic Leachate Procedure (TCLP). Lamp examples: OSRAM-Sylvania LU400/ECO Plus.

680-4 Demonstrate that the field wiring is properly installed, install the controller assembly, connect the wiring and turn on the controller.

680-5 All existing signal equipment with the exception of the signal controller and related equipment become the property of the Contractor. Deliver the controller and related equipment to the Signal shop, located at 4615 NW Loop 410 (corner of IH 410 and Callaghan Road) in San Antonio, Texas or to the Area Office as directed.

--Item 682--

682-1 Provide all signal heads from the same manufacturer. Pedestrian signals may be by a different manufacturer than the vehicle signal heads.

682-2 Cover all signal faces until placed in operation.

682-3 All pedestrian signal faces shall be single section LED Type. Die cast polycarbonate is acceptable in lieu of die cast aluminum. All mounting attachments shall be constructed of steel pipe and mounted as shown on the plans.

--Item 684--

684-1 Provide an extra 10' for each cable terminating in the controller cabinet. All cables shall be continuous without splices from terminal point to terminal point. All proposed signal cable shall be #12 AWG stranded copper.

--Item 686 & 687--

686-1 Provide all signal poles from the same manufacturer. Pedestrian poles may be from a different manufacturer.

--Item 6001--

Provide messages as directed by the Engineer.

Provide 2 solar powered changeable message signs for this project.